

\$ 180.32

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-071-20875-00-00  
Spot: NWNESE Sec/Twnshp/Rge: 20-20S-42W  
2310 feet from S Section Line, 990 feet from E Section Line  
Lease Name: GOERING Well #: 1-20  
County: GREELEY Total Vertical Depth: 5733 feet

Operator License No.: 33880  
Op Name: RAMSEY PROPERTY MANAGEMENT, L  
Address: 2932 NW 122ND ST STE # 4  
OKLAHOMA CITY, OK 73120

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	13.38	518		WITH 550 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/29/2010 10:00 PM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: TIM THOMPSON Company: CROWN CONSULTING Phone: (620) 388-4401

Proposed Plugging Method: 1ST PLUG AT 2350' WITH 75 SX CMT. 2ND PLUG AT 1350' WITH 150 SX CMT. 3RD PLUG AT 550' WITH 100 SX CMT. 4TH PLUG AT 60' WITH 40 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: NONE  
Date/Time Plugging Completed: 01/30/2010 12:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:  
1ST PLUG AT 2350' WITH 75 SX CMT. 2ND PLUG AT 1350' WITH 150 SX CMT. 3RD PLUG AT 550' WITH 100 SX CMT. 4TH PLUG AT 60' WITH 40 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

INVOICED  
DATE 3/03/10  
INV. NO. 2010060856  
RECEIVED  
FEB 08 2010  
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY BASIC ENERGY.

Plugged through: DP

District: 01  
RECEIVED  
FEB - 1 2010  
KCC DODGE CITY

Signed Stephen J Pfeifer  
(TECHNICIAN)

*AWZ*