

\$109.88

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-03004-00-00
Spot: E2E2E2NE Sec/Twnshp/Rge: 19-24S-4W
1320 feet from N Section Line, 320 feet from E Section Line
Lease Name: TUCKER Well #: 9
County: RENO Total Vertical Depth: 3381 feet

Operator License No.: 30364
Op Name: RESOURCE OPERATIONS, INC.
Address: BOX 9487
TULSA, OK 74157

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	459		N/A
PROD	7	3381		N/A

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/13/2009 8:00 AM
Plug Co. License No.: 7868 Plug Co. Name: KIZZAR WELL SERVICING, INC.
Proposal Rcvd. from: TOM ROSE Company: CONSULTANT Phone: (620) 786-4596

Proposed Plugging Method: PERF CASING AND RUN TUBING TO SPOT PLUGS

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL
Date/Time Plugging Completed: 11/13/2009 5:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

11/11/09 RAN TUBING INTO 3027' SPOTTED 50 SX OF CEMENT. 11/12/2009 PERF @ 650, RAN TUBING INTO 800' SPOTTED 50 SXS COMMON CEMENT WITH 4% CC, WAITED HOUR TAGGED CEMENT AT 725'. PULLED TUBING TO 650' CIRCULATED TO SURFACE WITH 185 SXS OF CEMENT. 11/13/09 CUT HEAD OFF AND RAN IN 360' OF 1 INCH TUBING BETWEEN THE 10 3/4 AND THE 7 INCH, PUMPED 100 SXS OF CEMENT. RAN TUBING INSIDE THE 7 INCH TO 60' CIRCULATED TO SURFACE WITH 35 SXS. 11/17/2009 CHECK TOP PLUGS, PLUGS WERE STILL AT SURFACE.

Perfs:

RECEIVED
FEB 10 2010
KCC WICHITA

INVOICED
DATE 3/03/10
INV NO. 2010060860

Remarks: COPELAND CEMENTING - FROM BURRTON--TICKET 334403 CASING PARTED REASON FOR PLUGGING. CASRING PARTED @ 1,159'-IMPRESSION BLOCK

Plugged through: TBG

District: 02

Signed B. J. Hope
(TECHNICIAN)

JK