


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Graham County. Sec. 4 Twp. 10 Rge. 25 (E) W (W)
Location as "NE/CNWxSWx" or footage from lines SE SW SW
Lease Owner Kimbark Exploration Company
Lease Name Paifer Well No. 1
Office Address Denver, Colorado
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 2-19-64 19
Plugging completed 2-22-64 19
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation Depth to top Bottom Total Depth of Well 4070 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	196'	None
				4-1/2"	4070'	3309'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to plug back @ 4036', sanded hole to 3960' and dumped 3 sacks of cement @ 3960' with dump bailer. Pulled 4 1/2" casing to 600' and circulated with gel mud. Pulled 4 1/2" casing to 190' and dumped 20 sacks of cement @ 190'. Pulled balance of 4 1/2" casing, bailed mud to 35', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
3-4-1964
MAR 4 1964

CONSERVATION DIVISION
Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (owner/contractor) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 29th day of February, 1964

My commission expires May 20, 1964
Milton J. Volin Notary Public.

15-065-03139-00-00

PFEIFER #1 WELL

LOCATION: SE SW SE SEC. 4
T-10-S, R-25-W
GRANAM COUNTY, KANSAS

SPUDED: 3/28/60
COMPLETED: 4/21/60

OWNER: KIMBARK EXPL. CO.
300 FILLMORE
DENVER, COLO.

CONTRACTOR: KIMBARK EXPL. CO.
300 FILLMORE
DENVER, COLO.

SURFACE CASING: 3 5/8" SS CASING CEMENTED @ 197' K.B. W/135 SX.
OIL STRING: 4 1/2" 9.5#, J-55, SS. CEMENTED @ 4070' K.B. W/50 SX CEMENT
AND 600' GAL LATEX.

LOG - FIGURES INDICATE BOTTOM OF FORMATION.

375	SHALE
2,150	SHALE & SAND
2,665	SHALE
3,095	SHALE & LIME
3,425	SHALE & LIME
3,723	SHALE & LIME
3,816	SHALE & LIME
3,955	SHALE & LIME
4,000	SHALE & LIME
4,120	SHALE & LIME
4,275	SHALE & LIME
4,285	SHALE & LIME

- ROTARY TOTAL DEPTH

RECEIVED
STATE CORPORATION COMMISSION
6-22-1964
JUN 22 1964
CONSERVATION DIVISION
Wichita, Kansas

THE UNDERSIGNED, W. K. ARBUCKLE, PRESIDENT OF KIMBARK EXPLORATION COMPANY, HEREBY CERTIFIES THAT THE ABOVE IS A TRUE AND CORRECT LOG OF THE FORMATIONS ENCOUNTERED IN DRILLING THE PFEIFER #1 WELL AS SHOWN IN THE DAILY DRILLING REPORTS.

KIMBARK EXPLORATION COMPANY

W. K. ARBUCKLE, PRESIDENT

STATE OF COLORADO)
CITY & COUNTY OF DENVER) SS

BE IT REMEMBERED THAT ON THIS 20TH DAY OF APRIL, 1960, BEFORE ME, A NOTARY PUBLIC, APPEARED PERSONALLY W. K. ARBUCKLE, PRESIDENT OF KIMBARK EXPLORATION COMPANY, A COLORADO CORPORATION, WHO IS PERSONALLY KNOWN TO ME AND KNOWN TO ME TO BE THE PRESIDENT OF SAID CORPORATION, AND THE SAME PERSON WHO EXECUTED THE FOREGOING INSTRUMENT, AND HE HAS DULY ACKNOWLEDGED THE EXECUTION OF THE SAME FOR AND ON BEHALF OF AND AS THE ACT AND DEED OF SAID CORPORATION.

WITNESS MY HAND AND OFFICIAL SEAL:
MY COMMISSION EXPIRES FEBRUARY 13, 1963

NOTARY PUBLIC