

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 8925
Name: Liberty Operations & Completions, Inc.
Address 1: 308 West Mill
Address 2: _____
City: Plainville State: KS Zip: 67663 + _____
Contact Person: Roger L. Comeau
Phone: (785) 434-4686
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Lansing/KC Depth to Top: 3422 Bottom: 3676 T.D. 3840
Arbuckle Depth to Top: 3771 Bottom: 3840 T.D. 3840
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 051-21291-00-00
Spot Description: _____
SW SW NW Sec. 25 Twp. 13 S. R. 20 East West
2,970 Feet from North / South Line of Section
4,950 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Ellis
Lease Name: Younger Well #: 4
Date Well Completed: 3-20-1977
The plugging proposal was approved on: _____ (Date)
by: Richard Williams (KCC District Agent's Name)
Plugging Commenced: 12/04/2009
Plugging Completed: 12/04/2009 @ 4:00pm

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Lansing/KC	Oil/Water	Surface	8 5/8	211	0
Arbuckle	Oil/Water	Production Casing	5 1/2	3836	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Rig up & ran perforation gun tag @ 2000' shot 2 holes, run # 2 shot 2 holes @ 1450', gun # 3 shot 2 holes @ 750' ran 2 7/8" tubing open ended. Ran 104 jts 3329 pump 100 sxs 60/40 4% gel with 200 lbs hulls. Pulled tubing to 2750' pump 150 sxs 60/40 4% gel and 100 lbs hulls. Pulled tubing 1250' pump 140 sxs 60/40 4% gel pulled remainder to tubing top of 5 1/2 csg. with 10 sxs 60/40 4% gel. Hooked up to surface head pump 55 sxs 60/40 4% gel. Cement coming up in cellar pump out cellar.

Plugging Contractor License #: 99977 Name: Quality Oil Well Cementing, Inc
Address 1: PO Box 32 Address 2: _____
City: Russell State: KS Zip: 67665 + _____
Phone: (785) 483-2025
Name of Party Responsible for Plugging Fees: Liberty Operations & Completions, Inc.
State of Kansas County, Rooks, ss.
Roger L. Comeau Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above described well, and that the same are true and correct, so help me God.

Signature: Roger L. Comeau

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 29 2010