


15-065-01144-00 20

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

GRAHAM County. Sec. 16 Twp. 10 Rge. 25 (E) W (W)  
Location as "NE/CNWxSWx" or footage from lines. C E/2 NE SE  
Lease Owner EMPIRE DRILLING COMPANY, ET AL  
Lease Name SCHREINER Well No. 1  
Office Address 400 BROWN BUILDING, WICHITA 2, KANSAS  
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE  
Date well completed FEBRUARY 3 1956  
Application for plugging filed FEBRUARY 3 1956  
Application for plugging approved FEBRUARY 3 1956  
Plugging commenced FEBRUARY 3 1956  
Plugging completed FEBRUARY 3 1956  
Reason for abandonment of well or producing formation DRY HOLE

If a producing well is abandoned, date of last production 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ELDON PETTY  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3970 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
SURFACE		0	175'	8 5/8"	175'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

BOTTOM PLUG SET AT 170' WITH 1 1/2 SACKS HULLS AND 15 SACKS OF CEMENT  
TOP PLUG @ 40' WITH 1/2 SACK OF HULLS AND 10 SACKS OF CEMENT.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor EMPIRE DRILLING COMPANY  
Address 400 BROWN BUILDING, WICHITA 2, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
I, DAN J. KORNFELD, (employee of owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Dan J. Kornfeld*  
DAN J. KORNFELD  
400 BROWN BUILDING, WICHITA 2, KANSAS  
(Address)

SUBSCRIBED AND SWORN to before me this 9TH day of FEBRUARY, 1956

My commission expires JUNE 7, 1956

*Charlotte Kletchka*  
CHARLOTTE KLETCHKA  
Notary Public.



**PLUGGING**  
FILE SEC. 16 T. 10 R. 25 W  
BOOK PAGE 37 LINE 2

2-10-56

L O G

COMPANY: EMPIRE DRILLING COMPANY, ET AL  
 CONTRACTOR: EMPIRE DRILLING COMPANY  
 FARM: SCHREINER NO. 1  
 LOCATION: C E/2 NE SE, SEC. 16-10-25  
 GRAHAM COUNTY, KANSAS  
 COMMENCED: 1-21-56  
 COMPLETED: 2-3-56

0	TO	195	SURFACE SHALE AND SAND
195	TO	980	SHALE AND SAND
980	TO	1340	SHALE AND SHELLS
1340	TO	1670	SHALE, SHELLS, SAND, PYRITE
1670	TO	2129	SHALE AND SHELLS
2129	TO	2170	ANHYDRITE
2170	TO	2655	SHALE AND SHELLS
2655	TO	3755	SHALE AND LIME
3755	TO	3970	LIME
3970			R.T.D.

SET 8 5/8" SURFACE CASING AT 175', CEMENTED WITH 115 SACKS OF CEMENT.

ELEVATION: 2504 K.B.

TOPS: ANHYDRITE 2129'; HEEBNER 3743'; TORONTO 3769'; LANSING 3788'; R.T.D. 3970'.

D.S.T. #1 3775 TO 3796'; D.S.T. #2 3796 TO 3820'; D.S.T. #3 3822 TO 3840'; D.S.T. #4 3902 TO 3930'; D.S.T. #5 3925 TO 3945'; D.S.T. #6 3935 TO 3970'.

D & A

C E R T I F I C A T I O N

I, DAN J. KORNFIELD, DO HEREBY CERTIFY THAT THE ABOVE AND FOREGOING IS A TRUE AND CORRECT COPY OF THE LOG ON THE SCHREINER NO. 1, C E/2 NE SE, SECTION 16, TOWNSHIP 10 SOUTH, RANGE 25 WEST, GRAHAM COUNTY, KANSAS, AS REFLECTED BY THE FILES OF THE EMPIRE DRILLING COMPANY.

*Dan J. Kornfeld*  
 DAN J. KORNFIELD



SUBSCRIBED AND SWORN TO BEFORE ME A NOTARY PUBLIC WITHIN AND FOR SEDGWICK COUNTY, KANSAS, THIS 19TH DAY OF FEBRUARY, 1956.

MY COMMISSION EXPIRES JUNE 7, 1956

*Charlotte Kletchka*  
 NOTARY PUBLIC  
 CHARLOTTE KLETCHKA

**PLUGGING**  
 FILE SEC 16 T 10 R 25W  
 BOOK PAGE 37 LINE 2

FEB 1956  
 2-10-56  
 NOTARY PUBLIC DIVISION  
 Wichita, Kansas