

15-065-01144-00-02

API NUMBER Drilled 1956

LEASE NAME Mary Webb

WELL NUMBER "P" #1 (OWWO)

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 16 TWP. 10 RGE. 25W (E) or (W)

COUNTY Graham

Date Well Completed

Plugging Commenced 5-18-94

Plugging Completed 5-19-94

COPY

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Ritchie Exploration, Inc.

ADDRESS 106 W. 34th Hays, KS 67601

PHONE# (913) 623-1453 OPERATORS LICENSE NO. 4767

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4014'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	175'	none
				4 1/2	4048'	800'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Sanded off bottom @ 3718' & dumped 4 sks cement. Shot @ 1911, 1613, & 1221, worked pipe.
Pumped 250# hulls w/60 sks cement & displaced to 850'. Shot @ 800', pulled 5 joints. Mixed
180 sks w/250# hulls & circulated to surface. Pulled rest of pipe, topped off well.
60/40 pos 10% gel. Plugging complete.
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ritchie Exploration, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 24th day of May, 19 94

James Stimpert
 Notary Public

My Commission Expires:



RECEIVED
 STATE CORPORATION COMMISSION
 MAY 25 1994
 CONSERVATION DIVISION
 Wichita, Kansas