

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-24417-00-00  
Spot: SWSWNW Sec/Twnshp/Rge: 19-20S-15W  
2970 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: IANNITTI Well #: 3  
County: BARTON Total Vertical Depth: 3875 feet

Operator License No.: 32278  
Op Name: TENGASCO, INC.  
Address: 1327 NOOSE RD PO BOX 458  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1103	0	400 SX CMT.
PROD	5.5	3873	1658	175 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/02/2010 7:30 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: TIM DICKSON Company: TENGASCO, INC. Phone: (785) 625-6374

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 400# hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/02/2010 12:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Bottom sanded off and topped with 5 sxs cement.  
Shot off casing at 1658' - pulled to 1600' - tied to casing and pumped 125 sxs cement with 300# hulls.  
Pulled casing to 696' - pumped 50 sxs cement with 100# hulls.  
Pulled to 150' - pumped 50 sxs cement - circulated to surface.  
Pulled casing - stayed full.

Perfs:

Top	Bot	Thru	Comments
3817	3818		
3806	3810		
3801	3804		
3797	3799		
3788	3790		

**INVOICED**  
DATE 3/25/10  
INV. NO. 2010060991

RECEIVED  
KANSAS CORPORATION COMMISSION

MAR 08 2010

Remarks: ALLIED CEMENTING COMPANY-TICKET #42082.

Plugged through: CSG

CONSERVATION DIVISION  
WICHITA, KS

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

CM

Form CP-2/3

MAR 05 2010