

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24578-00-00
Spot: NENENW Sec/Twnshp/Rge: 19-20S-15W
330 feet from N Section Line, 2310 feet from W Section Line
Lease Name: IANNITTI Well #: 8
County: BARTON Total Vertical Depth: 3883 feet

Operator License No.: 32278
Op Name: TENGASCO, INC.
Address: 1327 NOOSE RD PO BOX 458
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1149	0	425 SX CMT.
PROD	5.5	3881	1620	175 SX CMT.

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/26/2010 9:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: TIM DICKSON Company: TENGASCO, INC. Phone: (785) 625-6374

Proposed Plugging Method: Ordered 225 sxs 60/40 pozmix - 4% gel - 400# hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/26/2010 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded bottom and topped with 5 sxs cement.
Shot off casing at 1620' - pulled to 1600' - tied onto casing and pumped 125 sxs cement with 300# hulls.
Pulled to 720' - pumped 50 sxs cement with 100# hulls.
Pulled to 158' - pumped 50 sxs cement - circulated cement to surface - pulled casing - hole stayed full.

Perfs:

Top	Bot	Thru	Comments
3843	3848		
3826	3830		

INVOICED

DATE 3/25/10
INV. NO. 2010060991

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 08 2010

Remarks: ALLIED CEMENTING COMPANY.

CONSERVATION DIVISION
WICHITA, KS

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM