

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-137-20329-00-00
Spot: SWSENE Sec/Twnshp/Rge: 27-5S-21W
2970 feet from S Section Line, 990 feet from E Section Line
Lease Name: WILTROUT Well #: 1
County: NORTON Total Vertical Depth: 3655 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	266	0	105 SX
PROD	5.5	3649	0	100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/01/2010 11:00 AM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: KEN BUHLER Company: TRANS PACIFIC OIL CORPORATIO Phone: (316) 262-3596

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 600# hulls.
Perforated at 1830' and 1175'.

Plugging Proposal Received By: DARREL DIPMAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/01/2010 1:45 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 2500' - pumped 235 sxs 60/40 pozmix - 4% gel with 500# hulls - circulated to surface.
Pulled all tubing. Hooked to 5 1/2" casing - pumped 85 sxs 60/40 pozmix - 4% gel with 100# hulls. S.I.P. 200#.
Pumped 50 sxs 60/40 pozmix - 4% gel down 8 5/8" x 5 1/2" annulus.

Perfs:

INVOICED
DATE 3/25/10
INV. NO. 2010060992

RECEIVED
MAR 09 2010
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3781.

Plugged through: TBG

District: 04

Signed

Pat Bedore

(TECHNICIAN)

CM

MAR 04 2010

REPLACEMENT CARD


MARSHEL OIL & GAS, INC.
 816 BITTING BLDG.
 WICHITA, KS. 67202

#1 WILTROUT

27-5-21W
 SW SE NE

CONTR MURFIN DRILLING COMPANY CTY NORTON

GEOL ROBERT GENSCH FIELD RAY WEST



ELV 2231 KB SPD 1/9/84 CARD ISSUED 1/31/85 IP P 20 BO & 40 BWPD
 2226 GL DRLG COMP 1/15/84 ARB OH 3650-3655 -
 API 15-137-20,329

LOG	Tops	Depth/Datum
TOP		3231-1000
HEEB		3377-1146
TOR		3402-1171
LANS		3420-1189
BKC		3607-1376
ARB		3649-1418
RTD		3655-1424

8 5/8 " 266 / 175SX, 5 1/2 " 3649 / 100SX
 DST (1) 3412-3437 (LANS) / 34-35-30-30, REC 1020' GCSW, SIP
 1172-1132#, FP 80-364 / 465-537#
 DST (2) 3649-3655 (ARB) / 45-45-90-30, REC 320' CLEAN GSY
 OIL, 60' MCO, FSIP 927#, FP NA, TOOL PLUGGED ON CHART
 MICT - CO, (ARB OH), SWB DWN, SO, NAT, SET 2 7/8 " TBG AT
 3650', POP, P 20 BO & 40 BWP, 2/15/84

INFO RELEASED: 2/20/86 - WAS OIL WELL - TIGHT HOLE

COPYRIGHT 1985
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS