

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-20784-00-00
Spot: NWNE Sec/Twnshp/Rge: 24-27S-16W
4685 feet from S Section Line, 1994 feet from E Section Line
Lease Name: BUTLER-THOMPSON Well #: 3-24
County: KIOWA Total Vertical Depth: 4610 feet

Operator License No.: 5004
Op Name: VINCENT OIL CORPORATION
Address: 155 N MARKET STE 700
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	365		WITH 300 SX CMT
PROD	4.5	4603	2270	WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/01/2010 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP 250# HULLS & 30 SX CMT. PLUG AT 1030' WITH 15 SX GEL & 50 SX CMT. PLUG AT 390' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/01/2010 10:35 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PUMPED DOWN 4 1/2" CASING WITH 250# HULLS & 30 SX CMT. SHUT IN AT 300 PSI. TAG TOC @ 4150'. 1ST PLUG AT 1030' WITH 15 SX GEL, 50 SX CMT W/3% CC & 50# HULLS. 2ND PLUG AT 390' WITH 50 SX CMT & 50# HULLS. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4603	4610	OH	
4582	4586		
4454	4462		

INVOICED

DATE 3/25/10
INV. NO. 2010060993

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 08 2010

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING.

Plugged through: CSG

District: 01

Signed _____

Stephen J. Pfeifer
(TECHNICIAN)