

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-057-20666-00-00
Spot: SWSWNESW Sec/Twnshp/Rge: 21-27S-23W
1500 feet from S Section Line, 1640 feet from W Section Line
Lease Name: STEELE TRUST Well #: 1-21
County: FORD Total Vertical Depth: 5100 feet

Operator License No.: 5004
Op Name: VINCENT OIL CORPORATION
Address: 155 N MARKET STE 700
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	644		WITH 350 SX CMT

Well Type: DH UIC Docket No: Date/Time to Plug: 02/26/2010 8:00 AM
Plug Co. License No.: 5822 Plug Co. Name: VAL ENERGY, INC.
Proposal Rcvd. from: SCOTT Company: VAL ENERGY, INC. Phone: (316) 263-6688

Proposed Plugging Method: 1ST PLUG AT 1450' WITH 50 SX CMT. 2ND PLUG AT 660' WITH 50 SX CMT. 3RD PLUG AT 300' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: NONE
Date/Time Plugging Completed: 02/26/2010 5:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

1ST PLUG AT 1450' WITH 50 SX CMT. 2ND PLUG AT 660' WITH 50 SX CMT. 3RD PLUG AT 300' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:


INVOICED
DATE 3/25/10
INV. NO. 2010060993

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY QUALITY OILWELL CEMENTING.

Plugged through: DP

District: 01

Signed



(TECHNICIAN)

RECEIVED

MAR - 3 2010

KCC DODGE CITY

RECEIVED

MAR 15 2010

KCC WICHITA