

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-23613-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 5-17S-21W
5000 feet from S Section Line, 4925 feet from E Section Line
Lease Name: HIGGINS Well #: 1-5
County: NESS Total Vertical Depth: 4367 feet

Operator License No.: 31627
Op Name: WHITETAIL CRUDE, INC
Address: PO BOX 544 N HWY 283
NESS CITY, KS 67560

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1536		
SURF	8.625	332		WITH 180 SX CMT
PROD	4.5	1575	0	WITH 500 SX CMT

Well Type: SWD UIC Docket No: D26423.0 Date/Time to Plug: 02/19/2010 8:30 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: MIKE J. FRIZLER Company: WHITETAIL CRUDE, INC Phone: (785) 798-3641

Proposed Plugging Method: RUN TBG TO 1300'. PUMP 200# HULLS & CMT UNTIL IT CIRCULATES. PULL TBG & TOP OFF. TIE ONTO BACKSIDE AND PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/19/2010 10:30 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 1300' & PUMP 100 SX CMT & 200# HULLS. CMT DID NOT CIRCULATE. PULLED TBG TO 500' & PUMP 35 SX CMT. CMT CIRCULATED. PULLED TBG & TOPPED OFF WITH 15 SX CMT. STAYED FULL. TIED ONTO BACKSIDE & PUMPED 1 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
976	1298		

INVOICED
DATE 3/25/10
INV. NO. 2010060994

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 08 2010

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

CONSERVATION DIVISION
WICHITA, KS

District: 01

Signed Michael Maier
(TECHNICIAN)

RECEIVED
MAR - 2 2010

KCC DODGE CITY

Form CP-205