

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-23611-00-00  
Spot: NENESE Sec/Twnshp/Rge: 6-17S-21W  
2310 feet from S Section Line, 330 feet from E Section Line  
Lease Name: RUBY Well #: 1-6  
County: NESS Total Vertical Depth: 4330 feet

Operator License No.: 31627  
Op Name: WHITETAIL CRUDE, INC  
Address: PO BOX 544 N HWY 283  
NESS CITY, KS 67560

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	324		WITH 180 SX CMT
PROD	5.5	4329	0	WITH 125 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/18/2010 12:00 PM  
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC  
Proposal Rcvd. from: MIKE FRITZLER Company: WHITETAIL CRUDE, INC Phone: (785) 798-3641

Proposed Plugging Method: RUN TBG TO BOTTOM & PUMP 35 SX CMT & 150# HULLS. PULL TBG TO 1600' & CIRCULATE CMT. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/18/2010 12:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

2/16/10: RAN BOND LOG & FOUND CMT AT SURFACE. 2/18/10: RUN TBG TO 4039' & PUMPED 35 SX CMT & 150# HULLS. PULLED TBG & PUMPED 150 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 15 SX CMT. TIED ONTO BACKSIDE & PUMPED 25 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

INVOICED

DATE 3/25/10  
INV. NO. 2010060994

RECEIVED  
KANSAS CORPORATION COMMISSION

MAR 08 2010

CONSERVATION DIVISION  
WICHITA, KS

Remarks: UESD 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed Michael Maier  
(TECHNICIAN)

RECEIVED

MAR - 2 2010

KCC DODGE CITY

Form CP-275