

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-23403-00-00
Spot: SWSWE Sec/Twnshp/Rge: 17-11S-18W
330 feet from S Section Line, 2310 feet from E Section Line
Lease Name: FRISBIE I Well #: 1
County: ELLIS Total Vertical Depth: 3600 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	326	0	180 SX
PROD	5.5	3599	0	200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/25/2010 11:00 AM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: GARY SHARP Company: TRANS PACIFIC OIL CORPORATIO Phone: (316) 262-3596

Proposed Plugging Method: Ordered out 450 sxs 60/40 pozmix - 4% gel - 700# hulls.
Fluid 300' from surface.
Bad casing 1068' (cedar hills).
No squeeze records. Perforate 1700' - 1215' - 650'.

Plugging Proposal Received By: DARREL DIPMAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/25/2010 2:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated two holes each at 1700' - 1215' - 650'.
Ran tubing to 2500'. Bad casing at 1068'.
Quality Oil Well Cementing Company pumped 220 sxs cement with 300# hulls.
Pulled tubing to 1058' - pumped 110 sxs cement with 300# hulls - circulated cement.
PTOH. Squeezed 5 1/2" casing with 25 sxs cement.
Max. P.S.I. 400#. S.I.P. 100#.
Hooked up to backside - instant 500#.

Perfs:

Top	Bot	Thru	Comments
2911	3375		

NVOICED
DATE 3/25/10
INV. NO. 2010060992

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 08 2010
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)


CM

MAR 02 2010

ROBERT R. PRICE OPERATING, INC. #1 "1" FRISBIE 17-11-18W
 P.O. BOX 45442 TULSA, OK 74147 SW SW SE

CONTR RANGER DRILLING CO., INC. CTY ELLIS

GEOLOGICAL FIELD BEMIS-SHUTTS



ELV 1899 KB SPD 3/25/83 CARD ISSUED 6/16/83 IP P 3 BO & 88 BWPD
 1894 GL SHAW 2911-3148
 API 15-051-23,403 LKC 3149-3375 OA

LOG	Tops	Depth/Datum
ANH	1198 + 701
TOP	2879- 980
HEEB	3108-1209
TOR	3126-1227
LANS	3149-1250
BKC	3378-1479
ARB	3467-1568
LTD	3557-1658
RTD	3600-1701

8 5/8 " 326/180SX; 5 1/2 " 3599/200SX
 DST (1) 2883-2930 (SHAW, LKC) / OP 60", REC 90' WM, SIP
 836-733#, FP NA
 MICT - CO, PF (SHAW) 2911-3148 (EST) W/1 SPF & (LKC) 3149-
 3375 (EST) W/1 SPF, AC 4000G (15% HCL) & 27,500G (28%
 HCL), SWB LD, GSO, POP, P 3 BO & 88 BWPD (GR 31"), 5/17/83
 COMMINGLED

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS