

74.78

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-115-19159-00-00
Spot: NWNESWNE Sec/Twnshp/Rge: 20-21S-5E
3671 feet from S Section Line, 1878 feet from E Section Line
Lease Name: STRAIT RANCH Well #: 14
County: MARION Total Vertical Depth: 2301 feet

*the
man
3/29/10*

Operator License No.: 6655

Op Name: CRAWFORD, GARRY F. DBA CRAWFO

Address: PO BOX 727
EL DORADO, KS 67042

*CRAWFORD PRODUCTION
COMPANY*

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	205		100 SX
PROD 7		2279		125 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 03/18/2010 8:00 AM

Plug Co. License No.: 5870

Plug Co. Name: PHILLIPS WELL SERVICE, INC.

Proposal Rcvd. from: BRANCE CRAWFORD

Company:

Phone: (316) 323-5513

Proposed Plugging Method: AS PER KCC

Plugging Proposal Received By:

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 03/18/2010 5:10 PM

KCC Agent: SHANE JONES

Actual Plugging Report:

3/18/2010 PHILLIPS WELL SERVICE RIGGED UP ON THE WELL. THEY RAN 2" TUBING TO 2227'. CONSOLIDATED TIED ON AND PUMPED 50 SXS 60/40 POS W/4% GEL AND 4.5% CC. PHILLIPS THEN PULLED ALL BUT 8 JOINTS OF TUBING. CONSOLIDATED RAN ITS WIRE LINE DONE AND TAGGED CEMENT @ 2020'. CONSOLIDATED THEN TIED ON TO THE 2" TUBING AND TRIED TO CIRCULATE WATER UP AND AROUND THE BACKSIDE. THEY DID NOT GET CIRCULATION UP THE BACKSIDE. PHILLIPS PULLED THE REMAINING TUBING, AND CONSOLIDATED TIED ON TO THE 7". THEY WERE ABLE TO GET FLUID TO CIRCULATE UP THE BACKSIDE THIS WAY. THEY CHANGED TO CEMENT AND CIRCULATED 110 SXS. CONSOLIDATED SHUT IN THE CASING WITH A VALVE. THEY FINISHED AROUND 5:10 PM USING A TOTAL OF 160 SXS OF 60/40 POS W/4% GEL TK #23317. 3/22/2010 I CHECKED TOP PLUG FINDING IT AT THE SURFACE OF THE CASING.

Perfs:

Top	Bot	Thru	Comments
2279	2301	OH	

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 26 2010
CONSERVATION DIVISION
WICHITA, KS

INVOICED
DATE 3/29/10
INV. NO. 2010060999

Remarks: TA HAD BEEN APPROVED FOR 6 MONTH IN ACCORDANCE WITH COMPLIANCE AGREEMENT WITH THE DISITRICT 2 OFFICE. WAS ORIGINALLY DENIED DUE TO 10 YEAR RULE. SJ.

Plugged through: CSG

District: 02

Signed

(TECHNICIAN)

sk