

83, 69

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-23094-00-00
Spot: N2NWNWSE Sec/Twnshp/Rge: 29-25S-5E
2494 feet from S Section Line, 2351 feet from E Section Line
Lease Name: STAPLETON A Well #: 63
County: BUTLER Total Vertical Depth: 2575 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	240		
PROD	5.5	2571		
CISP 5.5 @ 2400' w/ 2 sk				

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/23/2010 8:00 AM
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORPORATION Phone: (316) 655-1997

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: NONE
Date/Time Plugging Completed: 02/23/2010 8:00 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 565', CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 35 SXS 60/40 POZMIX 4% GEL, 3% CC AND DISPLACED IN CASING. TAGGED CEMENT @ 504'. ON WIRELINE SHOT SQUEEZE HOLES @ 210' & 130', COULD NOT ESTABLISH CIRCULATION. RIH W/TBG @ 315', CONSOLIDATED ESTABLISHED CIRCULATION AND MIXED & PUMPED 55 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 2/23/2010, 3:00 P.M.

Perfs:

Top	Bot	Thru	Comments
2462	2467		VIOLA
670	684		ADMIRE
554	558		ADMIRE

INVOICED
DATE 3/29/10
INV. NO. 2010061002

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 26 2010
CONSERVATION DIVISION
WICHITA, KS

Remarks: CONSOLIDATED CEMENT TICKET #23305

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

JK