

#143.46

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-21133-00-00
Spot: NENE Sec/Twnshp/Rge: 28-27S-11W
660 feet from N Section Line, 660 feet from E Section Line
Lease Name: HAMMEKE Well #: 1
County: PRATT Total Vertical Depth: 4414 feet

Operator License No.: 30481
Op Name: APOLLO ENERGIES, INC.
Address: 10378 N 281 HWY
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	410		WITH 500 SX CMT
PROD	4.5	4414	2010	WITH 300 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/10/2010 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 3700' & 4 SX CMT ON TOP OF SAND BRIDGE. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 440' WITH 75 SX CMT. PLUG AT 40' WITH 30 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/10/2010 11:20 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 3700' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT W/3% CC & 50# HULLS. 2ND PLUG AT 440' WITH 75 SX CMT W/50# HULLS. 3RD PLUG AT 40' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3850	3856		
3754	3760		

INVOICED
DATE 4/02/10
INV. NO. 2010061006

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 29 2010

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

CONSERVATION DIVISION
WICHITA, KS

Plugged through: CSG

District: 01

Signed

Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
MAR 22 2010
KCC DODGE CITY