

#130.68

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-151-22125-00-00  
Spot: NWSENW Sec/Twnshp/Rge: 8-27S-11W  
3630 feet from S Section Line, 3540 feet from E Section Line  
Lease Name: HOLLAND Well #: C-2  
County: PRATT Total Vertical Depth: 4021 feet

Operator License No.: 30481  
Op Name: APOLLO ENERGIES, INC.  
Address: 10378 N 281 HWY  
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	235		WITH 300 SX CMT
COND	10.75	232		
PROD	4.5	4015	3520	WITH 125 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/12/2010 9:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: JIM BYERS Company: APOLLO ENERGIES Phone: (620) 672-9001

Proposed Plugging Method: SAND TO 3600' & 4 SX CMT. PLUG AT 810' WITH 15 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT. PUMP DOWN 8 5/8" X 10 3/4" ANNULUS WITH 100 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/12/2010 12:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

\*\*4 1/2" CASING WAS PARTED @ 3520'. 2600'-3520' FULL OF HOLES.\*\* SANDED BACK TO 3600' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. 1ST PLUG AT 810' WITH 15 SX GEL & 50 SX CMT W/3% CC & 100# HULLS. NO RETURNS. 2ND PLUG AT 300' PUMPED 20 SX GEL, BROKE CIRCULATION, SPOTTED 50 SX CMT W/3% CC & 100 #HULLS. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG PUMP DOWN 8 5/8" X 10 3/4" ANNULUS WITH 50 SX CMT. COMMUNICATED WITH INSIDE OF 8 5/8" CASING. TOP OUT 8 5/8" CASING & 8 5/8" X 10 3/4" ANNULUS WITH 50 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3686	3800		

**INVOICED**  
DATE 4/02/10  
INV. NO. 2010061006

RECEIVED  
KANSAS CORPORATION COMMISSION  
MAR 29 2010

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: TBG

CONSERVATION DIVISION  
WICHITA, KS

District: 01

Signed Stephen J. Pfeifer  
(TECHNICIAN)

RECEIVED  
MAR 22 2010  
KCC DODGE CITY