

133.25

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-21872-00-00
Spot: SWSENWNE Sec/Twnshp/Rge: 29-16S-20W
1060 feet from N Section Line, 1700 feet from E Section Line
Lease Name: EISENHOUR Well #: 1
County: RUSH Total Vertical Depth: 4100 feet

Operator License No.: 9860
Op Name: CASTLE RESOURCES, INC.
Address: BOX 87
SCHOENCHEN, KS 67667

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	216		WITH 165 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 03/15/2010 12:00 AM
Plug Co. License No.: 34190 Plug Co. Name: VISION OIL & GAS SERVICES LLC
Proposal Rcvd. from: BOB MICHELSON Company: VISION OIL & GAS SERVICES LLC Phone: (316) 425-3534

Proposed Plugging Method: 1ST PLUG AT 1460' WITH 50 SX CMT. 2ND PLUG AT 580' WITH 50 SX CMT. 3RD PLUG AT 250' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: RICHARD LACEY WitnessType: NONE
Date/Time Plugging Completed: 03/15/2010 2:00 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

1ST PLUG AT 1460' WITH 50 SX CMT. 2ND PLUG AT 580' WITH 50 SX CMT. 3RD PLUG AT 250' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Perfs:

INVOICED

DATE 4/02/10
INV. NO. 2010061007

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY SOS

Plugged through: DP

District: 01

RECEIVED

MAR 25 2010

KCC DODGE CITY

Signed

Richard W. Lacey

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 29 2010

CONSERVATION DIVISION
WICHITA, KS

Form CP-233