

#125.29

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23520-00-00
Spot: E2SESW Sec/Twnshp/Rge: 4-8S-23W
660 feet from S Section Line, 2970 feet from E Section Line
Lease Name: SAND CREEK Well #: 5
County: GRAHAM Total Vertical Depth: 3855 feet

Operator License No.: 34055
Op Name: H & M PETROLEUM CORPORATION
Address: 13570 MEADOWGRASS DR STE 101
COLORADO SPGS, CO 80921

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3760		
SURF	8.625	210	0	165 SX CMT
T1	2.875	3783		
PC		1940		175 SX CMT
PROD	5.5	3851	0	175 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/19/2010 10:30 AM
Plug Co. License No.: 34115 Plug Co. Name: SCHIPPERS OILFIELD SERVICES, LLC
Proposal Rcvd. from: SCOTT SCHIPPERS Company: H&M PETROLEUM CORPORATION Phone: (719) 590-6060

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 300# hulls - 9 sxs gel.
Port collar 1940' w/175 sxs cement.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/19/2010 12:15 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Tied onto 5 1/2" - pumped 125 sxs cement with 300# hulls - followed with 9 sxs gel - followed with 180 sxs cement - full - shut in with 700# P.S.I. Backside with 5 sxs cement. Shut in - full.

Perfs:

Top	Bot	Thru	Comments
3782	3784		
3778	3780		

INVOICED

DATE 4/02/10
INV. NO. 2010061011

RECEIVED
MAR 31 2010
KCC WICHITA

Remarks: SOS CEMENTING COMPANY-TICKET #430.

Plugged through: CSG

District: 04

Signed *Marvin Mills*
(TECHNICIAN)

CM

MAR 19 2010

Replacement Card

M PETROLEUM CORP
O SPRINGS CO 80621

4-08S-23W
C E/2 SE SW
KANSAS

#5 SAND CREEK

Spot: C E2 SE SW API 15-065-23520
Lat/Long: 39.38052 -99.89328

OIL

GRAHAM
3/4 N & 2 W OF HILL CITY KS
MONTGOMERY EAST

12/08/2008 Spd: 12/16/2008 Drig Cp: 12/28/2008 Issued: 10/12/2009 Revised: 11/02/2009

Copyright 2009 Independent Oil & Gas Service, Inc. Wichita, KS

Side 1

Status: P 3 BO & 15 BWPD, LKC 3616-3630 OA, 2/18/2009

Reasons: INFO RELEASED: 11/2/2009 - WAS OIL

Well - TIGHT HOLE

Driller: WW DRILLING #8

Operator: RICHARD P. BELL

Location: 2311 KB, 2306 GL, 2309 DF

Information: (L-Log, S-Sample, D-Driller)

ANH	1972 +339
TOP	3334 -1023
HEEB	3543 -1232
LANS A	3585 -1274
LANS D	3627 -1316
MUN CR	3693 -1382
STARK	3760 -1449
PBTD	3760 -1449
BKC	3794 -1483
RTD	3855 -1544

Csg: 8-5/8" 210 / 165 SX (ALT 2), 5-1/2" 3851 / 175 SX,
MULTI STAGE COLLAR AT 1940 / 175 SX

Find:

COMMENT: WELL LOC BASED ON 3-D SEISMIC
INTRPRTN; PROPOSED START 12/13/2008; MI &
RURT 12/16/2008; S.D. HOLIDAY 12/19/2008;
RESUMED OPERS 12/26/2008

SHOWS: 3616-3621 (LKC C LM, TR PNPT PORO,
SPTY STN, SFO-THICK BLK STRINGY, TR
FLOATING FREE OIL, NO ODOR), 3627-3630 (LKC
D LM, TR PORO, FR SPTY STN, FR PNPT SFO
WHEN BRKN, NO ODOR), LKC E (LM, NO PORO,
LT EDGE STN, NSFO, NO ODOR), 3654-3661
(LKC F LM, SME VUG PORO, SLI SPTY STN,
NSFO, NO ODOR), 3748-3752 (LKC J LM,
PNPT-VUG PORO, PR PERM, SPTY STN,
SFO-BLK STRINGY, NO ODOR), LKC K (LM, NO
VIS PORO, BLK SPTY ASPHLTC RESDU, NO
ODOR)