

118,95

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-22011-00-00
Spot: SWNWNE Sec/Twnshp/Rge: 11-22S-12W
990 feet from N Section Line, 2310 feet from E Section Line
Lease Name: WILLINGER Well #: 5-B
County: STAFFORD Total Vertical Depth: 3660 feet

Operator License No.: 6039
Op Name: L.D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	335		WITH 250 SX CMT
PROD	5.5	3648	2236	WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/10/2010 2:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 3300' & 5 SX CMT. PLUG AT 630' WITH 10 SX GEL & 50 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/10/2010 4:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SAND TO 3280' & 5 SX CMT WITH DUMP BAILER. 1ST PLUG AT 647' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 365' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3568	3576		VIOLA
3350	3364		LANSING
3349	3351		LANSING

INVOICED

DATE 4/02/10
INV. NO. 2010061014

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 29 2010

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

CONSERVATION DIVISION
WICHITA, KS

Plugged through: CSG

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED
MAR 15 2010
KCC DODGE CITY

Form CC-4