

#118.63

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-23613-00-00  
Spot: S2 Sec/Twnshp/Rge: 6-22S-11W  
1320 feet from S Section Line, 2260 feet from W Section Line  
Lease Name: SUSIE Well #: 1  
County: STAFFORD Total Vertical Depth: 3650 feet

Operator License No.: 32432  
Op Name: LA VETA OIL & GAS, LLC  
Address: 312 N. BUFFALO  
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	219		WITH 275 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/21/2010 10:30 PM  
Plug Co. License No.: 33323 Plug Co. Name: PETROMARK DRILLING, LLC  
Proposal Rcvd. from: SCOTTY PILAND Company: PETROMARK DRILLING, LLC Phone: (316) 734-8977

Proposed Plugging Method: 1ST PLUG AT 3550' WITH 50 SX CMT. 2ND PLUG AT 540' WITH 50 SX CMT. 3RD PLUG AT 240' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: NONE  
Date/Time Plugging Completed: 03/22/2010 12:45 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

1ST PLUG AT 3550' WITH 50 SX CMT. 2ND PLUG AT 540' WITH 50 SX CMT. 3RD PLUG AT 240' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: DP

**INVOICED**

DATE 4/02/10  
INV. NO. 2010061015

District: 01

RECEIVED  
MAR 25 2010

KCC DODGE CITY

Signed Eric MacLaren  
(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION

MAR 29 2010

CONSERVATION DIVISION  
WICHITA, KS

  
Form OP 2/3