

\$164.13

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-093-20567-00-00  
Spot: SWNENENE Sec/Twnshp/Rge: 9-26S-36W  
350 feet from N Section Line, 350 feet from E Section Line  
Lease Name: LEE Well #: 24-4  
County: KEARNY Total Vertical Depth: 5050 feet

Operator License No.: 8061  
Op Name: OIL PRODUCERS INC. OF KANSAS  
Address: 1710 WATERFRONT PKWY  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1850		WITH 2 SX CMT
CIBP		3750		WITH 2 SX CMT
SURF	8.625	541		WITH 200 SX CMT
PROD	5.5	5049	0	WITH 150 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/24/2010 9:00 AM  
Plug Co. License No.: 34091 Plug Co. Name: BLACKHAWK WELL SERVICE, LLC  
Proposal Rcvd. from: BARRY WALTERS Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE DURRANT WitnessType: NONE  
Date/Time Plugging Completed: 03/24/2010 1:00 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

**\*\*LEFT SOME TBG & RODS IN WELL BELOW CIBP.\*\*** CIBP @ 3750' WITH 2 SX CMT. CIBP @ 1850' WITH 2 SX CMT. PERFORATE @ 700'. ESTABLISH INJECTION RATE. HAD PARTIAL RETURNS OUT ANNULUS. PUMP 80 SX CMT, 20 BALL SEALERS, THEN 60 SX CMT. PRESSURE TO 500#. PUMP 30 SX CMT DOWN ANNULUS. PRESSURE TO 300# & HELD.

Perfs:

Top	Bot	Thru	Comments
4490	5000		ST LOUIS

**INVOICED**  
DATE 4/02/10  
INV. NO. 2010061019

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

RECEIVED  
MAR 25 2010  
KCC DODGE CITY

Signed Steve Durrant  
RECEIVED (TECHNICIAN)  
KANSAS CORPORATION COMMISSION

MAR 29 2010

CONSERVATION DIVISION  
WICHITA, KS