

\$141.38

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-21661-00-00  
Spot: NWSESESE Sec/Twnshp/Rge: 14-27S-10W  
495 feet from S Section Line, 495 feet from E Section Line  
Lease Name: D D DYCHE Well #: 1  
County: KINGMAN Total Vertical Depth: 4350 feet

Operator License No.: 3911  
Op Name: RAMA OPERATING CO., INC.  
Address: 101 S MAIN ST  
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	318		180 SX
PROD	5.5	4399	2212	190 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: \_\_\_\_\_  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKES TESTING & SALVA Company: MIKE KELSO Phone: (620) 938-2537

Proposed Plugging Method: PER KCC RULES & REGS

Plugging Proposal Received By: SHANE JONES Witness Type: PARTIAL  
Date/Time Plugging Completed: 02/16/2010 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

2/15/2010 SANDED BACK TO 3960', SPOTTED 5 SXS OF CEMENT ON TOP OF SAND, CUT PIPE OFF AT 2212'. 2/16/2010 PULLED CASING PIPE TO 1460' SPOTTED 35 SXS OF CEMENT, PULLED CASING TO 940' SPOTTED 35 SXS OF CEMENT. PULLED CASING TO 365' CIRCULATED 160 SXS OF CEMENT TO THE SURFACE. 2/17/2010 CEMENT FELL BACK 55' NO FLUID, DROPPED 15 SXS IN SURFACE TO TOP OFF.

Perfs:

Top	Bot	Thru	Comments
4279	4298	CSG	VIOLA
4018	4042	CSG	MISS

INVOICED  
DATE 3/09/10  
INV. NO. 2010060891  
RECEIVED  
FEB 26 2010  
KCC WICHITA

Remarks: COPELAND CEMENTING OUT OF GREAT BEND, TICKET #35839 60/40 POZ MIX W/4% GEL GPS: LAT: 37.690320, LONG: -98.375010

Plugged through: CSG

District: 02

Signed B. J. Hope  
(TECHNICIAN)

✓