

#70.20

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-049-19249-00-00
Spot: SWNWNW Sec/Twnshp/Rge: 23-30S-10E
4181 feet from S Section Line, 4652 feet from E Section Line
Lease Name: BAUDER Well #: A 1
County: ELK Total Vertical Depth: 2160 feet

Operator License No.: 3591
Op Name: TRIBOULET, ED DBA C & E OIL CO.
Address: RR1 BOX 1B2
MOLINE, KS 67353

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF		125		

Well Type: EOR UIC Docket No: E22224.1 Date/Time to Plug: 02/15/2010 2:00 PM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: 50' at 2010', 50' at 1200' and 500' to surface.

Plugging Proposal Received By: DUANE SIMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/15/2010 4:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Casing was parted around 1053'. Ran 2" to 1063' and could not go any deeper. They were on outside of casing. Pulled up to 1053' and spotted 65 sacks of cement with cottonseed hulls. Very little circulation and than cement went down 4.5". Pulled 2" to 560' and circulated cement to surface. Pulled 2" and topped well off. A total of 125 sacks of cement were used to plug this well.

Perfs:

INVOICED
DATE 3/09/10
INV. NO. 2010060893

RECEIVED
FEB 16 2010 DAS
KCC Chanute Dist. #3

RECEIVED
FEB 22 2010
KCC WICHITA

Remarks: WE KNOW THE CASING WAS PARTED BECAUSE OPERATOR TRIED RUNNING TUBING AND PACKER WITH SPEAR ON IT. THEY COULD NOT GET DOWN CASING. HAD MUD ON SPEAR.

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)