

\$ 78.33

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-24085-00-00
Spot: NWNWNENE Sec/Twnshp/Rge: 30-31S-4E
5052 feet from S Section Line, 1063 feet from E Section Line
Lease Name: RICHARDSON Well #: 5-30
County: COWLEY Total Vertical Depth: 2410 feet

Operator License No.: 31451
Op Name: TROY JACO, INC.
Address: 200 N TRAVIS ST STE 412 PO BOX 147
SHERMAN, TX 75091

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	234		135 SX
PROD	4.5	2410	1160	185 SX

Well Type: EOR UIC Docket No: E27532.1 Date/Time to Plug: 01/26/2010 8:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, INC.
Proposal Rcvd. from: JOE BURNETT Company: GRESSEL OILFIELD SERVICE INC. Phone: (620) 463-5161

Proposed Plugging Method: PER KCC RULES AND REGULATIONS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 01/26/2010 12:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK 50' ABOVE PERFS @ 2340', DUMP BAILED 5 SXS CEMENT ON TOP. CUT 4-1/2" CASING @ 1,160', LAYED DOWN 29 JOINTS 4-1/2" CASING. RIH W/TUBING @ 305', GRESSEL OILFIELD SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 225 SXS CLASS A COMMON. 2% CC TO SURFACE, CEMENT CIRCULATED. PLUG DOWN 12:00 PM, 1/26/2010. GRESSEL CEMENT TICKET #34432.

Perfs:

Top	Bot	Thru	Comments
2389	2394	CSG	

INVOICED
DATE 3/09/10
INV. NO. 2010060895

RECEIVED
FEB 05 2010
KCC WICHITA

Remarks: E-27532, DROPPED 6 JOINTS 2-3/8" TBG IN WELL BY ACCIDENT AFTER CEMENT HAD CIRCULATED TO SURFACE.

Plugged through: TBG

District: 02 Signed Duane Krueger (TECHNICIAN)

✓JK