

\$ 145.20

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-21410-00-00
Spot: E2SWSE Sec/Twnshp/Rge: 36-33S-6W
660 feet from S Section Line, 1650 feet from E Section Line
Lease Name: STRUBLE Well #: 36D-3
County: HARPER Total Vertical Depth: 4483 feet

Operator License No.: 4941
Op Name: UNION VALLEY PETROLEUM CORPOR
Address: 10422 PINTO LN
ENID, OK 73701

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4314		W/ 2 SX
SURF	8.625	272		175 SX
PROD	5.5	4440	2340	250 SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/12/2009 4:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: SET CIBP 50' ABOVE TOP PERF, CAP WITH 2 SKS CMT. RECOVER CASING. SPOT 35 SKS PLG AT 1250'. SPOT 35 SKS PLUG AT 650', CIRC. CMT FROM 320'-0'.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: NONE
Date/Time Plugging Completed: 08/12/2009 4:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A 45 SK CMT PLUG AND 200# OF COTTON SEED HULLS WAS PUMPED TO SQUEEZE THE PERFS OFF. MAX PRESSURE 1800#. TOC inside 5.5, 3050'. RECOVERED CASING FROM 2340', PULLED TO 1250', WHERE 35 SKS OF CMT WAS SPOTTED. PULLED CASING TO 320' AND CIRCD CMT TO SURFACE. PULLED REMAINING CASING AND TOPPED OFF CMT.

Perfs:

Top	Bot	Thru	Comments
3528	3532		


INVOICED
DATE 3/09/10
INV. NO. 2010060896

RECEIVED
FEB 18 2010
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING 60/40 4% GEL TICKET #'S 2484 & 2485

Plugged through: CSG

District: 02

Signed 
(TECHNICIAN)

JK