

\$ 106.57

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-079-19014-00-00
Spot: SESESE Sec/Twnshp/Rge: 14-22S-2W
330 feet from S Section Line, 330 feet from E Section Line
Lease Name: SPERLING P A Well #: 1
County: HARVEY Total Vertical Depth: 3279 feet

Operator License No.: 5822
Op Name: VAL ENERGY, INC.
Address: 200 W DOUGLAS AVE STE 520
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	2980		
COND	20	132		
L1	4.5	431		3456' to 3025'
PROD	7	3118		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/08/2009 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: _____ Witness Type: PARTIAL
Date/Time Plugging Completed: 12/10/2009 3:15 PM KCC Agent: SHANE JONES

Actual Plugging Report:

12/4 KELSO SANDED OFF THE BOTTOM TO 2880' AND CAPPED W/7SXS. 12/7 KELSO PERFORATED CASING @ 400'. 12/10 KELSO CREW ARRIVED AT 10:00 AM AND ORANGE PEELED 8 5/8" TO 7" AND WELDED ON A 2" COLLAR. KELSO'S STARTED TUBING IN THE HOLE AT 12:15 PM. THEY RAN TUBING TO 400'. COPELAND TIED ON TO TUBING AND USED 15 BBL WATER TO LOAD HOLE. COPELAND CIRCULATED FLUID UP THE 7" AND THE 8 5/8" CASING. COPELAND PUMPED CEMENT DOWN THE TUBING USED 130 SXS TO CIRCULATE OUT THE 7". THEY THEN SHUT IN THE 7" AND USED ANOTHER 20 SXS TO CIRCULATE OUT THE 8 5/8". KELSO'S THEN PULLED TUBING, AND RIGGED UP TO RUN 1" TUBING DOWN BETWEEN THE 8 5/8" AND 20". THEY RAN 1" TO 75' AND TAGGED SOLID. PULLED UP TO 60' AND CIRCULATED 130 SXS TO SURFACE. COPELAND THEN TOPPED OFF THE 7" WITH ANOTHER 30 SACKS. 12/11 I CHECKED TOP PLUG AND FOUND IT DOWN 110'. COPELAND CIRCULATED 35 SXS TO TOP OFF CASING @ 3:00 PM. TK #36275 USED 345 SXS 60/40 POS W/4% GEL.

Perfs:

Top	Bot	Thru	Comments
3424	3428	CSG	
3401	3408	CSG	
3258	3286	CSG	
2975	2984	CSG	
2958	2962	CSG	
2930	2936	CSG	

INVOICED
DATE 3/09/10
INV. NO. 2010060897
RECEIVED
FEB 08 2010
KCC WICHITA

Remarks: PBTD 3449', CIBP @ 3050, CIBP @ 2970, SQUEEZED W/100SXS @ 2975-2984 GPS: LAT: 38.131390 LONG: - 97.501290

Plugged through: TBG

District: 02

Signed [Signature]
(TECHNICIAN)

JK