

126. 82

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-20168-00-00
Spot: NWSESW Sec/Twnshp/Rge: 20-28S-5W
990 feet from S Section Line, 3630 feet from E Section Line
Lease Name: ALTHOUSE A Well #: 4
County: KINGMAN Total Vertical Depth: 3902 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3800		
SURF	8.625	256		200 SX
PROD	5.5	3876	2612	150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING & SALVAGE Phone: (620) 938-2943

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 02/09/2010 2:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

CIBP @ 3800' DUMPED 4 SXS OF CEMENT ON TOP WITH DUMP BAILER 2-8-10 CUT CASING OFF AT 2612'. 2/9/2010 PULLED CASING TO 850' SPOTTED 35 SXS CEMENT, PULLED CASING TO 375' CIRCULATED 220 SXS OF CEMENT TO SURFACE. 2/10/10 TAGGED CEMENT INSIDE SURFACE PIPE AT 30' DOWN, FILLED WITH QWIKCRETE AND WILL WELD PLATE ON TOP OF SURFACE PIPE.

Perfs:

Top	Bot	Thru	Comments
3876	3902	OH	MISS OH

INVOICED
DATE 3/09/10
INV. NO. 2010060898

RECEIVED
FEB 26 2010

Remarks: COPELAND CEMENTING - OUT OF GREAT BEND, TICKET #35836 -- 60/40 4% POS MIX

KCC WICHITA

Plugged through: CSG

District: 02

Signed B Hope

(TECHNICIAN)

JK