

78.20

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-23322-00-00
Spot: NWSWNENE Sec/Twnshp/Rge: 2-26S-4E
4327 feet from S Section Line, 1160 feet from E Section Line
Lease Name: PAULSON A Well #: 120
County: BUTLER Total Vertical Depth: 2406 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	1850		
CIBP	5.5	2340		
SURF	8.625	272		175 SX
PROD	5.5	2375		335 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/14/2009 8:00 AM
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORPORATION Phone: (316) 655-1997

Proposed Plugging Method: 1992 AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: NONE
Date/Time Plugging Completed: 12/14/2009 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 1,635', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 50 SXS CLASS A COMMON 3% CC & DISPLACED IN CASING. WAITED 2-HOURS, TAGGED CEMENT @ 1175', RIH W/TBG @ 344', CONSOLIDATED ESTABLISHED CIRCULATION, MIXED & PUMPED 42 SXS 60/40 POZMIX 4% GEL, CEMENT CIRCULATED. LAYED DOWN TBG, TOPPED WELL OFF W/14 SXS. PLUG DOWN 5:00 P.M., 12-14-2009. CONSOLIDATED OIL WELL SERVICES TICKET #23145. 56 SXS TOTAL ON TOP PLUG.

RECEIVED
JAN 19 2010
KCC WICHITA

Perfs:

Top	Bot	Thru	Comments
2375	2406	OH	ARBUCKLE OH
1992	2112	CSG	LKC OH
1665	1668	CSG	

INVOICED
DATE 3/09/10
INV. NO. 2010060898

Remarks: CEMENT @ SURFACE ON BACKSIDE 5.5" CASING. LAT: 37.82196, LONG: 96.95644

Plugged through: TBG

District: 02 Signed Duane Krueger
(TECHNICIAN)

JK