

# 84.50

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-19671-00-00  
Spot: SENESESW Sec/Twnshp/Rge: 33-25S-5E  
754 feet from S Section Line, 2871 feet from E Section Line  
Lease Name: PIERPOINT A Well #: 97  
County: BUTLER Total Vertical Depth: 2600 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 1700 WATERFRONT PKWY BLDG 500  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	207		160 SX
L1	4.5	2488		170 SX
PROD	5.5	2599		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/02/2009 8:00 AM  
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.  
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORPORATION Phone: (316) 655-1997

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL  
Date/Time Plugging Completed: 12/02/2009 3:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2,500', CONSOLIDATED WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 57 SXS CLASS A 3% CC & DISPLACED IN CASING. WAITED 2-HOURS, TAGGED CEMENT @ 1930'. PERFORATED SQUEEZE HOLES @ 300-301'. RIH W/TUBING @ 500', CONSOLIDATED MIXED & PUMPED 30 SXS 60/40 POZMIX 4% GEL 3% CC AND DISPLACED IN CASING. WAITED 2-HRS, TAGGED CEMENT @ 515'. RIH W/TBG 2 310', CONSOLIDATED ESTABLISHED CIRCULATION, MIXED & PUMPED 50 SXS 60/40 POZMIX 4% GEL, CEMENT CIRCULATED. LAYED DOWN TBG, SWEDGED INTO 5-1/2" CASING, MIXED & PUMPED 100 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 3:00 P.M., 12-2-2009. SHUT DOWN PRESSURE 300#, SHUT IN PRESSURE 100#.

Perfs:

Top	Bot	Thru	Comments
2522	2530	CSG	VIOLA

INVOICED  
DATE 3/09/10  
INV. NO. 2010060898  
RECEIVED  
JAN 19 2010  
KCC WICHITA

Remarks: CONSOLIDATED OIL WELL SERVICES TICKET # 23138. LAT: 37.82684, LONG: 96.88694

Plugged through: TBG

District: 02

Signed Duane Krueger  
(TECHNICIAN)

JK