

# 166.47

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-097-20496-00-00  
Spot: SWSE Sec/Twnshp/Rge: 22-30S-18W  
660 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: UNRUH ALTON B Well #: 2  
County: KIOWA Total Vertical Depth: 5122 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 1700 WATERFRONT PKWY BLDG 500  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5100		
SURF	8.625	552		WITH 400 SX CMT
PROD	5.5	5106	3706	WITH 260 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/11/2010 3:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: TRACY BLACK Company: VESS OIL Phone: (316) 682-1537

Proposed Plugging Method: SAND TO 5025' & 5 SX CMT. PLUG AT 1120' WITH 15 SX GEL & 50 SX CMT. PLUG AT 580' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/11/2010 4:40 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SAND TO 4970' WITH 5 SX CMT. 1ST PLUG AT 1134' WITH 15 SX GEL & 50 SX CMT.  
2ND PLUG AT 580' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5106	5122	OH	MISS DOLO OH
5076	5090		MISS CHERT

INVOICED  
DATE 3/09/10  
INV. NO. 2010060898

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID & CEMENT.

Plugged through: CSG

RECEIVED  
JAN 19 2010

KCC WICHITA

District: 01

Signed Eric MacLaren  
(TECHNICIAN)

RECEIVED  
JAN 12 2010  
KCC DODGE CITY

Form CP-2/3