

7 166.40

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-097-20523-00-00  
Spot: SESE Sec/Twnshp/Rge: 22-30S-18W  
660 feet from S Section Line, 660 feet from E Section Line  
Lease Name: UNRUH ALTON B Well #: 3  
County: KIOWA Total Vertical Depth: 5120 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 1700 WATERFRONT PKWY BLDG 500  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	538		WITH 400 SX CMT
PROD	5.5	5087	2552	WITH 260 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/06/2010 9:38 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: TRACY BLACK Company: VESS OIL CORPORATION Phone: (316) 215-1873

Proposed Plugging Method: SAND TO 5030' & 5 SX CMT. PLUG AT 1120' WITH 15 SX GEL & 50 SX CMT. PLUG AT 560' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/06/2010 11:25 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SAND TO 5030' & 5 SX CMT. 1ST PLUG AT 1133' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 570' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5087	5120	OH	MISS DOLOMITE O

INVOICED  
DATE 3/09/10  
INV. NO. 2010060898

RECEIVED  
JAN 11 2010  
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID & CEMENT

Plugged through: CSG

District: 01

Signed Eric MacLaren  
(TECHNICIAN)

RECEIVED  
JAN - 7 2010  
KCC DODGE CITY

Form CR 2/3