

80,34

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-19601-00-00
Spot: SESENE SW Sec/Twnshp/Rge: 9-25S-5E
1478 feet from S Section Line, 2923 feet from E Section Line
Lease Name: WILSON A Well #: 49
County: BUTLER Total Vertical Depth: 2472 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	2152		
COND	12.5	770		
PROD	6.625	2441		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/17/2009 8:00 AM
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORPORATION Phone: (316) 655-1997

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 12/17/2009 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2,450', CONSOLIDATED WELL SERVICES ESTABLISHED CIRCULATION. MIXED & PUMPED 75 SXS CLASS A COMMON 3% CC & DISPLACED IN CASING. TAGGED CEMENT @ 2240', RIH W/TBG @ 2,100' CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 50 SXS CLASS A COMMON 3% CC & DISPLACED IN CASING. TAGGED CEMENT @ 2,140'. RIH W/TBG @ 2,100', CONSOLIDATED MIXED & PUMPED 50 SXS CLASS A COMMON 3% CC & DISPLACED IN CASING. TAGGED CEMENT @ 1,566. RIH W/TBG @ 630', CONSOLIDATED MIXED & PUMPED 100 SXS CLASS A COMMON 35 CC & DISPLACED IN CASING. TAGGED CEMENT @ 540'. PERFORATED SQUEEZE HOLES @ 300-301', RIH W/TBG @ 310', CONSOLIDATED ESTABLISHED CIRCULATION, MIXED & PUMPED 200 SXS 60/40 POZMIX 4% GEL TO SURFACE, CEMENT CIRCULATED. LAYED DOWN TBG, SWEDGED INTO 5-1/2" CASING, MIXED & PUMPED 265 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 P.M. 12-17-2009.

Perfs:

Top	Bot	Thru	Comments
2454	2464	CSG	

INVOICED
DATE 3/09/10
INV. NO. 2010060898
RECEIVED
JAN 19 2010
KCC WICHITA

Remarks: CONSOLIDATED OIL WELL SERVICES TICKET #23249. GPS: LAT: 37.88682, LONG: 96.88703

Plugged through: TBG

District: 02 Signed Duane Krueger
(TECHNICIAN)

154