

\$164.94

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-20036-00-01
Spot: SENE Sec/Twnshp/Rge: 7-30S-18W
1980 feet from N Section Line, 660 feet from E Section Line
Lease Name: PARKIN OWWO Well #: 1-C
County: KIOWA Total Vertical Depth: 5075 feet

Operator License No.: 5004
Op Name: VINCENT OIL CORPORATION
Address: 155 N MARKET STE 700
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	429		WITH 325 SX CMT
PROD	4.5	5075	2600	WITH 175 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 02/18/2010 1:02 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: PAT LIVINGSTON Company: VINCENT OIL Phone: (316) 262-3573

Proposed Plugging Method: SAND TO 4800' & 4 SX CMT. PLUG AT 1180' WITH 15 SX GEL & 50 SX CMT. PLUG AT 450' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/18/2010 2:12 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

PUMPED 200# HULLS & 30 SX CMT. TOC @ 4700'. 1ST PLUG AT 1180' WITH 15 SX GEL, 50# HULLS, 50 SX CMT W/2% CC. 2ND PLUG AT 450' WITH 50# HULLS & 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5029	5031		
5021	5027		
4953	4957		
4848	4859		MARM

INVOICED
DATE 3/09/10
INV. NO. 2010060899

RECEIVED
FEB 22 2010

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING.

KCC WICHITA

Plugged through: CSG

District: 01

Signed Eric MacLaren
(TECHNICIAN)

RECEIVED
FEB 19 2010

KCC DODGE CITY