

#154.67

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-21824-00-00
Spot: NESWNENW Sec/Twnshp/Rge: 6-14S-31W
736 feet from N Section Line, 1804 feet from W Section Line
Lease Name: HESS Well #: 3
County: GOVE Total Vertical Depth: 4759 feet

Operator License No.: 32016
Op Name: WELLS, RODGER D. DBA PIONEER RES
Address: 80 WINDMILL DR.
PHILLIPSBURG, KS 67661

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	216		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 01/29/2010 6:00 PM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: KIRBY Company: PIONEER RESOURCES Phone: (785) 543-5556

Proposed Plugging Method: Ordered 220 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE BASYE WitnessType: NONE
Date/Time Plugging Completed: 01/29/2010 8:10 PM KCC Agent: BRUCE BASYE

Actual Plugging Report:
1st. Plug at 2460' w/25 sxs.
2nd. Plug at 1500' w/100 sxs.
3rd. Plug at 270' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.

Perfs:
INVOICED
DATE 3/09/10
INV. NO. 2010060900

RECEIVED
FEB 12 2010
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.
Plugged through: DP

District: 04

Signed Bruce D. Leape
(TECHNICIAN) cm

FEB 01 2010