

\$ 134.45

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-22131-00-00  
Spot: N2NENE Sec/Twnshp/Rge: 4-30S-6W  
330 feet from N Section Line, 660 feet from E Section Line  
Lease Name: SIMON Well #: 1-4  
County: KINGMAN Total Vertical Depth: 4137 feet

Operator License No.: 31337  
Op Name: WILDCAT OIL & GAS LLC  
Address: 10286 SW 170TH AVE  
NASHVILLE, KS 67112

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	3657		
SURF	8.625	266		60/40-190 SX
T1	2.375	3605		
PROD	4.5	4134	3420	60/40-40 SXS, CLASS H-125 SX

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/10/2008 12:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: SAND BACK TO 3528' AND 4 SKS OF CMT. REC CASING, 35 SKS 1050', 35 SKS 650', CIRC. 310-0

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL  
Date/Time Plugging Completed: 10/10/2008 2:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:  
THE PERFS WERE COVERED WITH SAND TO 3490', AND CAPPED WITH 4 SKS OF SAND. THE CASING WAS RECOVERED FROM 3420', AND PULLED TO 1050', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 650', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 315, WHERE CMT WAS CIRCD TO SURFACE.


Perfs:

Top	Bot	Thru	Comments
3726	3730	CSG	
3690	3694	CSG	
3578	3585	CSG	

RECEIVED  
FEB 18 2010  
KCC WICHITA  
INVOICED  
DATE 3/09/10  
INV. NO. 2010060902

Remarks: QUALITY OIL WELL CEMENTING. 60/40 POZ  
Plugged through: CSG

District: 02

Signed  (TECHNICIAN)

1/4