

\$64.94

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21427-00-00
Spot: NWNESESW Sec/Twnshp/Rge: 2-28S-5W
1140 feet from S Section Line, 2160 feet from W Section Line
Lease Name: TIP TOP CREDIT UNION Well #: 4
County: KINGMAN Total Vertical Depth: 1998 feet

Operator License No.: 7775
Op Name: WILTON PETROLEUM, INC.
Address: PO BOX 391
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	230		150 SXS CMT
PROD	4.5	1989	1400	100 SXS CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 31528 Plug Co. Name: KELSO, MIKE OIL, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE KELSO Phone: (620) 628-4466

Proposed Plugging Method: PER KCC RULES & REGULATIONS

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL
Date/Time Plugging Completed: 02/11/2010 3:30 PM KCC Agent: B. J. HOPE

Actual Plugging Report:
2/10/10 SANDED BACK TO 1880' TOPPED WITH 4 SXS OF CEMENT. 2/11/2010 AT 1050' SPOTTED 35 SXS OF 60/40/4% POS MIX. AT 550' CIRCULATED 265 SXS OF 60/40/4% POS MIX TAGGED 1 HOUR LATER AT 300' CAME BACK WITH WITH 150 SXS OF COMMON CEMENT 3% CC, 150 LBS OF COTTON SEED HULLS AND CIRCULATED TO SURFACE. 2/12/2010 TAGGED CEMENT AT SURFACE. FIRST TRIED TO CUP PIPE OFF AT 1400' WITH KNIFE, OPERATOR DID NOT THINK HE WAS LOOSE SO MOVED UP TO 1200' AND IT CAME LOOSE, BUT WHEN WE GOT SALT TO SURFACE WITH TOP SALT PLUG WE CAME OUT OF HOLE TO SEE WHERE WE WERE AT, WE HAD THE EXTRA 200' THAT THE OPERATOR DID NOT ACCOUNT FOR. THAT IS THE REASON FOR THE ODD DEPTHS ON THE PLUGS, AND THE EXTRA CEMENT USED TO PLUG WELL BORE.

Perfs:
INVOICED
DATE 3/09/10
INV. NO. 2010060903

RECEIVED
FEB 18 2010
KCC WICHITA

Remarks: COPELAND CEMENTING OUT OF BURRTON, TICKET #34442
Plugged through: CSG

District: 02 Signed B. J. Hope (TECHNICIAN)

JK