

\$153.95

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-23036-00-00
Spot: E2SWSWSE Sec/Twnshp/Rge: 6-32S-11W
330 feet from S Section Line, 2080 feet from E Section Line
Lease Name: BARBER COUNTY Well #: 1
County: BARBER Total Vertical Depth: 4737 feet

Operator License No.: 33168
Op Name: WOOLSEY OPERATING COMPANY, LL
Address: 125 N MARKET STE 1000
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	289		WITH 240 SX CMT
COND	20	41		
PROD	4.5	4716	3280	WITH 160 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 02/01/2010 1:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND BACK TO 4240' & 4 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 320' WITH 75 SX CMT. PLUG AT 40' WITH 30 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/01/2010 2:50 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 4250' & PUT 4 SX CMT ON TOP OF SAND BRIDGE. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT W/3% CC & 50# HULLS. 2ND PLUG AT 320' WITH 75 SX CMT WITH 50# HULLS. 3RD PLUG AT 40' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4338	4343		
4330	4335		
4322	4326		
4312	4318		
4297	4306		

INVOICED
DATE 3/09/10
REV. NO. 2010060904

RECEIVED
FEB 19 2010

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: CSG

KCC WICHITA

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
FEB - 5 2010

KCC DODGE CITY

Form CP 7/3