

TO:  
 STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION - PLUGGING  
 130 SOUTH MARKET, SUITE 2078  
 WICHITA, KANSAS 67202

API Well Number: 15-033-20548-00-03

Spot: SESWNE Sec/Twnshp/Rge: 28-34S-16W

3190 feet from S Section Line, 1920 feet from E Section Line

Lease Name: BEELEY TRUST

Well #: 1-28

County: COMANCHE

Total Vertical Depth: 6013 feet

Operator License No.: 33168

String Size Depth (ft) Pulled (ft) Comments

Op Name: WOOLSEY OPERATING COMPANY, LL

CIBP .5530

Address: 125 N MARKET STE 1000

CIBP 5685

WICHITA, KS 67202

SURF 8.625 410

WITH 225 SX CMT

PROD 5.5 6007 2030

WITH 100 SX CMT

Well Type: DH

UIC Docket No:

Date/Time to Plug: 02/15/2010 12:22 PM

Plug Co. License No.: 31925

Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: CARL W DURR

Company: WOOLSEY OPERATING

Phone: (620) 886-5606

Proposed SAND TO 5110' WITH 5 SX CMT. PLUG AT 960' WITH 15 SX GEL & 50 SX CMT. PLUG AT 440' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Method:

Plugging Proposal Received By: ERIC MACLAREN

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 02/15/2010 1:43 PM

KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SAND TO 5110' & 5 SX CMT. 1ST PLUG AT 960' 15 SX GEL, 50# HULLS, & 50 SX CMT W/2% CC. 2ND PLUG AT 440' WITH 50# HULLS & 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5810	5815		
5732	5742		
5715	5721		
5600	5612		
5160	5200		

INVOICED  
 DATE 3/09/10  
 INV. NO. 2010060904

RECEIVED  
 FEB 22 2010  
 KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: CSG

District: 01

Signed Eric MacLaren

(TECHNICIAN)

RECEIVED  
 FEB 18 2010

KCC DODGE CITY

FORM CR-103