

# 170.63

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-23180-00-00  
Spot: NWSENW Sec/Twnshp/Rge: 11-34S-12W  
1450 feet from N Section Line, 1650 feet from W Section Line  
Lease Name: FARNEY TRUST Well #: 1  
County: BARBER Total Vertical Depth: 5250 feet

Operator License No.: 33168  
Op Name: WOOLSEY OPERATING COMPANY, LL  
Address: 125 N MARKET STE 1000  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	214		WITH 200 SX CMT
PROD	4.5	5103	3430	WITH 210 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/09/2010 9:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 4640' & PUT 4 SX CMT ON TOP OR PUMP 300# HULLS & 20 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 240' WITH 75 SX CMT. PLUG AT 40' WITH 30 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/09/2010 11:15 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 4640' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT W/3% CC & 50# HULLS. 2ND PLUG AT 240' WITH 75 SX CMT & 50# HULLS. 3RD PLUG AT 40' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4744	4762		MISSISSIPPIAN
4716	4740		MISSISSIPPIAN
4690	4700		MISSISSIPPIAN

INVOICED  
DATE 3/09/10  
INV NO. 2010060904

RECEIVED  
KANSAS CORPORATION COMMISSION

MAR 01 2010

CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING

Plugged through: CSG

District: 01

Signed Stephen J. Pfeifer  
(TECHNICIAN)

RECEIVED  
FEB 18 2010  
KCC DODGE CITY

Form CP-2/3