

157.26

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-20666-00-01
Spot: NESE Sec/Twnshp/Rge: 1-32S-12W
1980 feet from S Section Line, 660 feet from E Section Line
Lease Name: LUKENS Well #: 1OWWO
County: BARBER Total Vertical Depth: 4654 feet

Operator License No.: 33168
Op Name: WOOLSEY OPERATING COMPANY, LL
Address: 125 N MARKET STE 1000
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	227		WITH 185 SX CMT
PROD	4.5	4361	3020	WITH 160 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 02/03/2010 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND BACK TO 4200' & PUT 4 SX CMT ON TOP OF SAND BRIDGE OR PUMP 200# HULLS & 20 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 260' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT

Plugging Proposal Received By: STEVE PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/03/2010 1:10 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PUMP 200# HULLS & 20 SX CMT. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT 3% CC & 50# HULLS. 2ND PLUG AT 260' WITH 50 SX CMT & 50# HULLS. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4278	4294		
4256	4264		

INVOICED
DATE 3/09/10
INV. NO. 2010060904

RECEIVED
FEB 19 2010

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.
Plugged through: CSG

KCC WICHITA

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
FEB - 5 2010
KCC DODGE CITY