

\$ 186.88

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-033-20523-00-01  
Spot: NESWSEW Sec/Twnshp/Rge: 33-34S-16W  
2080 feet from N Section Line, 1750 feet from W Section Line  
Lease Name: OLLER Well #: 1OWWO  
County: COMANCHE Total Vertical Depth: 5750 feet

Operator License No.: 33168  
Op Name: WOOLSEY OPERATING COMPANY, LL  
Address: 125 N MARKET STE 1000  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	421		
PROD	4.5	5728	4050	WITH 250 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/11/2010 9:45 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: CARL W. DURR Company: WOOLSEY OPERATING Phone: (316) 267-4379

Proposed Plugging Method: SAND BACK TO 5150' & WITH 2 SX CMT. PLUG AT 880' WITH 12 SX GEL & 50 SX CMT. PLUG AT 450' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/11/2010 11:17 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SANDED TO 5150' WITH 4 SX CMT. 1ST PLUG AT 880' WITH 12 SX GEL, 50# HULLS, 3% CC, 50 SX CMT. 2ND PLUG AT 450' WITH 50# HULLS & 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5296	5300		
5290	5292		
5278	5280		
5240	5264		
5226	5234		
5203	5212		
5198	5200		

INVOICED  
DATE 3/09/10  
INV. NO. 2010060904

RECEIVED  
FEB 19 2010

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

KCC WICHITA

Plugged through: CSG

District: 01

Signed Eric MacLaren  
(TECHNICIAN)

RECEIVED  
FEB 12 2010  
KCC DODGE CITY

Form CP-2/3