

\$ 66.40

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-21078-00-01

Spot: SWNWNE

Sec/Twnshp/Rge: 3-26S-15W

2002 feet from S Section Line,

3659 feet from E Section Line

Lease Name: GRIZZEL C

Well #: 1

County: PRATT

Total Vertical Depth: 2043 feet

Operator License No.: 5046

Op Name: RAYMOND OIL COMPANY, INC.

Address: PO BOX 48788

WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
--------	------	------------	-------------	----------

SURF	8.625	409		WITH 300 SX CMT
------	-------	-----	--	-----------------

PROD	5.5	4509	2400	WITH 175 SX CMT
------	-----	------	------	-----------------

Well Type: EOR

UIC Docket No: E27061.1

Date/Time to Plug: 01/26/2010 3:30 PM

Plug Co. License No.: 31529

Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO

Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed
Plugging
Method:

SAND BACK 50' ABOVE PERFS & PUT 5 SX CMT ON TOP OF SAND BRIDGE. PLUG AT 1050' WITH 20 SX GEL & 50 SX CMT. PLUG AT 440' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 01/26/2010 4:20 PM

KCC Agent: STEVE PFEIFER

Actual Plugging Report:

Perfs:

SANDED BACK TO 4320' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. 1ST PLUG AT 1050' WITH 20 SX GEL & 50 SX CMT. 2ND PLUG AT 440' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

INVOICED

DATE 3/09/10
INV. NO. 2010060905

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: TBG

RECEIVED

FEB 19 2010

KCC WICHITA

District: 01

Signed

Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED

FEB - 5 2010

KCC DODGE CITY

Form 0823