

\$105.24

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-115-30007-00-00
Spot: N2SENE Sec/Twnshp/Rge: 22-19S-1E
3590 feet from S Section Line, 889 feet from E Section Line
Lease Name: SCHROEDER Well #: 2
County: MARION Total Vertical Depth: 3238 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	2827		
SURF	8.625	165		85 SX
PROD	5.5	3236	405	65 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/15/2010 10:00 AM
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION
Proposal Rcvd. from: DOUG WARD Company: _____ Phone: (620) 654-7149

Proposed Plugging Method: AS PER KCC

Plugging Proposal Received By: _____ WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/15/2010 4:00 PM KCC Agent: SHANE JONES

Actual Plugging Report:

2/15/2010 AMERICAN ENERGIES MOVED IN AND RAN TOOLS TO 2825'. THEY THEN DROPPED SAND AND LET IT FALL. AFTER LUNCH THEY WENT IN AND TAGGED SAND @ 2720' AND CAPPED IT W/5 SXS. THEY THEN PULLED 405' OF 5.5" CASING. THEY THEN RAN 270' OF 2" TUBING IN THE HOLE. COPELAND TIED ON AND CIRCULATED CEMENT TO SURFACE. AMERICAN ENERGIES PULLED TUBING. THE HOLE STILL STANDING FULL OF CEMENT. THEY CLEANED UP AND RIGGED DOWN. THEY FINISHED @ 4:00 PM USING 175 SXS OF 60/40 POX W/4% GEL. TK #34446.

Perfs:

Top	Bot	Thru	Comments
2783	2833	CSG	MISSISSIPPIAN

INVOICED
DATE 3/09/10
INV. NO. 2010060906


RECEIVED
FEB 26 2010

Remarks: CASING LEAK GPS: LAT: 38.386890, LONG: -97.300940

Plugged through: TBG

KCC WICHITA

District: 02

Signed  (TECHNICIAN)

15K