

36.86

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-125-22158-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 30-33S-16E
330 feet from S Section Line, 660 feet from W Section Line
Lease Name: KLUMP Well #: 30-1
County: MONTGOMERY Total Vertical Depth: 1134 feet

Operator License No.: 5817
Op Name: BENSON MINERAL GROUP, INC.
Address: 1560 BROADWAY STE 1900
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1134		

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/02/2009 8:00 AM
Plug Co. License No.: 34203 Plug Co. Name: PIRATE WELL SERVICE, LLC
Proposal Rcvd. from: JAMES PERKINS Company: PIRATE WELL SERVICE, LLC Phone: (620) 374-2301

Proposed Plugging Method: Run cement string and attempt to shot off and salvage 4-1/2" casing. Stage cement plugs

Plugging Proposal Received By: RUSSELL HINE Witness Type: NONE
Date/Time Plugging Completed: 06/02/2009 5:00 PM KCC Agent: RUSSELL HINE

Actual Plugging Report:

Ran cement string to 1130'. Pumped gel to condition well bore. Pumped 15 sacks at 1130'. Pulled cement string and shot 4 1/2" at 300'. Attempted to pull 4-1/2" but could not. Ran cement string back in to 630'. Pumped 50' plug (5sacks). Pulled cement string. Shot well at 200' and 40', attempted to pull 4-1/2", could not. Ran cement string back in to 300' and filled to surface. Pulled cement string and topped off well. 48 sacks of portland, 15 sacks of gel

Perfs:

RECEIVED
FEB 25 2010 RHH
KCC Chanute Dist. #3

INVOICED
DATE 3/09/10
INV. NO. 2010060908

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 01 2010
CONSERVATION DIVISION
WICHITA, KS

Remarks: 48 SXS CEMENT, 15 SXS. OF GEL

Plugged through: TBG

District: 03

Signed Russell Hine
(TECHNICIAN)