

\$ 116.77

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-22013-00-00
Spot: NWSENE Sec/Twnshp/Rge: 24-13S-18W
3630 feet from S Section Line, 1040 feet from E Section Line
Lease Name: KIPPES Well #: 1
County: ELLIS Total Vertical Depth: 3593 feet

Operator License No.: 6931
Op Name: BOWMAN OIL COMPANY, A GENERAL
Address: 805 CODELL RD
CODELL, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	575	0	150 SX
PROD	4.5	3700	0	250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/04/2010 9:30 AM
Plug Co. License No.: 6931 Plug Co. Name: BOWMAN OIL COMPANY, A GENERAL PARTNERSHIP
Proposal Rcvd. from: DON BOWMAN Company: BOWMAN OIL COMPANY Phone: (785) 434-2286

Proposed Plugging Method: Ordered 375 sxs 60/40 pozmix - 4% gel - 500# hulls - 7 sxs gel.
PBTB 3593'.
Denied TA-complaint and lease worked up by Pat Staab.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/04/2010 12:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

LK Wireline perfed at 1850' - 1385' - 780' - 550'.
Quality rigged to casing - pumped 45 sxs 60/40 pozmix - 4% gel with 250# hulls mixed in - followed with 7 sxs gel - followed with 150 sxs 60/40 pozmix - 4% gel with 250# hulls.
Pumped to pressured with Max. P.S.I. 500#. S.I.P. 200#.
Rigged to 8 5/8" - pumped 50 sxs cement.
Max. P.S.I. 400#. S.I.P. 300#.
Opened 4 1/2" - swedge well went on small vacuum.
Pumped an additional 50 sxs cement to top off 4 1/2" casing.
Hole standing full.

Perfs:

Top	Bot	Thru	Comments
3476	3523	OH	Arbuckle

RECEIVED
JAN 06 2010
KCC WICHITA
INVOICED

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3605.

DATE 3/09/10
INV. NO. 2010060910

Plugged through: CSG

District: 04

Signed [Signature]
(TECHNICIAN) CM

JAN 04 2010

K&E PETROLEUM INC

816 UNION CENTER

WICHITA, KS 67202

#1 KIPPES

24-13-18W
50'W, C NW SE NE


CONTR ABERCROMBIE DRILLING CTY ELLIS

GEOL TOM SATTER FIELD GROSS NE

E 2133 KB CM 7/28/80 CARD ISSUED 10/30/80 IP P 77.93 80 & 5.87

2128 GL 15-051-22,013

BWPD
LANS 3475 $\frac{1}{2}$ -3523 OA



API

LOG	TOPS	DEPTH	DATUM
HEEB		3381	-1248
TOR		3402	-1269
LANS		3429	-1296
BKC		3658	-1525
CONG		3694	-1561
LTD&RTD		3713	-1580

8 5/8" 574.5; 4 $\frac{1}{2}$ " 3699.77

DST (1) 3594-3644 (PENN W/STR PKR) /
30-30-30-30, REC 2'M, SIP 55-44
FP 44-44/44-44#

DST (2) 3464-3512 (LKC W/STR PKR) /
30-45-30-60, 600' FL, 120'
HO & GCM, 60' VHO & GCM, 420'
MGCO, SIP 1002-914 BLDG, FP
121-243/243-265#

DST (3) 3408-63 (LKC W/STR PKR) / 30-45-
30-60, 230' FL, 80' HO & GCM,
120' MGCO, 30' FROGGY MDY O, SIP
837-760#..FP 55-110/132-143#

(OVER)

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS