

\$ 92.30

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-20827-00-02
Spot: W2W2SW Sec/Twnshp/Rge: 6-30S-11W
1320 feet from S Section Line, 330 feet from W Section Line
Lease Name: JEWELL A Well #: 1-6
County: BARBER Total Vertical Depth: 2840 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6200 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2255		WITH 5 SX CMT
SURF	8.625	251		WITH 252 SX CMT
PROD	4.5	2839	1773	WITH 150 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/26/2010 9:00 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING REPORT

Plugging Proposal Received By: STEVE PFEIFER WitnessType: NONE
Date/Time Plugging Completed: 02/26/2010 10:00 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

CIBP @ 2255' & PUT 5 SX CMT ON TOP OF CIBP. 1ST PLUG AT 740' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 280' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2748	2778		INDIAN CAVE
2618	2624		RED EAGLE
2316	2318		
2309	2318		WREFORD

INVOICED
DATE: 3/09/10
INV NO. 2010060912

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 08 2010

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

CONSERVATION DIVISION
WICHITA, KS

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
MAR - 1 2010
KCC DODGE CITY

Form CP-2/3