

170.82

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22477-00-01
Spot: NWSWSE Sec/Twnshp/Rge: 34-33S-14W
800 feet from S Section Line, 2190 feet from E Section Line
Lease Name: WHEAT A Well #: 2-34
County: BARBER Total Vertical Depth: 5256 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6200 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3915		WITH 2 SX CMT
CIBP		4340		WITH 2 SX CMT
SURF	8.625	1099		WITH 525 SX CMT
PROD	5.5	5243	3000	WITH 275 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/02/2010 11:00 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: KEITH SHANAHAN Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: CIBP @ 3900' & 2 SX CMT. PLUG AT 1120' WITH 15 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/02/2010 1:10 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 3915' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 1120' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4774	4790		MISSISSIPPIAN
4708	4734		MISSISSIPPIAN
3936	3942		DOUGLAS SAND

INVOICED
DATE 3/09/10
INV NO. 2010060912

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 08 2010

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

CONSERVATION DIVISION
WICHITA, KS

Plugged through: TBG

District: 01

RECEIVED
MAR - 3 2010
KCC DODGE CITY

Signed Steve Pfeifer
(TECHNICIAN)

