

7169.1

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-071-20754-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 12-17S-43W
2310 feet from S Section Line, 2310 feet from E Section Line
Lease Name: SCHARDEIN Well #: 1-12
County: GREELEY Total Vertical Depth: 5200 feet

Operator License No.: 33962
Op Name: DEKA EXPLORATION, INC.
Address: PO BOX 14057
OKLAHOMA CITY, OK 73113

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4900		WITH 2 SX CMT
SURF	8.625	238		WITH 250 SX CMT
PROD	5.5	5196	0	WITH 100 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/22/2010 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: BURL COLLINSWORTH Company: DEKA EXPLORATION Phone: (405) 823-3506

Proposed
Plugging
Method:

CIBP @ 4900' WITH 2 SX CMT. FILL 5 1/2" WITH CMT FROM 2650'-0'. CHECK BACKSIDE.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/22/2010 5:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

5 1/2" WAS PERFORATED @ 2630' & SQUEEZED WITH 250 SX CMT. PERFORATED @ 1350' WITH 300 SX CMT. PERFORATED @ 900' CIRCULATED CMT TO SURFACE WITH 275 SX CMT. CIBP @ 4900' WITH 2 SX CMT. RAN TBG TO 2673' & CIRCULATE CMT TO SURFACE IN 2 STAGES USING 250 SX CMT & 200# HULLS. TOOH W/TBG & TOP OFF 5 1/2" CASING WITH 6 SX CMT. PUMP 4 SX CMT DOWN ANNULS TO 500#.

Perfs:

Top	Bot	Thru	Comments
5080	5084		
4985	4992		

INVOICED
DATE 3/09/10
INV. NO. 2010060915

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 01 2010

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED
FEB 18 2010

KCC DODGE CITY

Signed

Ken Jehlik

(TECHNICIAN)

Form CS-23